G. R. S. IX-5]

Previous references.

Reserve for

File No. 76—18

1918.

(L. B.) 27136

Serial Nos. 1—2

Later references.

LB55—18 83 11, 20, 24+28

LB. 41-22 (3—6)

GENERAL AND REVENUE SECRETARIAT.

Serial Nos. 1—2

Part B for February 1919.

SUBJECT.

Construction of a bridge across the Vadli Stream on the Hassan-Periapatna-Cauvery road

---

From the Chief Engineer No. B. 522 dy 16/1/19

-elicit sanction of Govt. to an estimate amounting to Rs 25,140/- for constructing a bridge across the Vadli Stream on the Hassan Periyapatna-Cauvery Road.

2 2 To the Chief Engineer. } No 11065—7
" Controller. } dy 27/2/19
" President, Dt. Bd. Mysore }

Sanctions the estimate

W D 1250—GRB—30,000 - 25—19.

B. A. Narasimhayya 1/3/19

G. R. S. 12]

9956

General and Revenue Secretariat. | LB File No. 76 of 1918.

Serial No.	
	Genuine signed by the Presidt, that the Estimate for Rs 2540 has also been appd by the Dkpb. at the meeting held on 20.12.1918, through the reduction in the file dated 23.8.18. There is a provision of Rs 5000/- for the current year. The Estimate may therefore be sanctd and Subd to H.H. [illegible].

MK 23.1.19

2758/25.1.9

Rwsecy)

Temp. Member & Dewan -,

hm 24.1. MK

4278/1.2.18

3) May be sanctioned

[illegible] 30/1/19

4) Papers U

J. hm

[illegible]

M 3/2

5) Submitted with a.d.s.w. Please see flag N.

MK 10/2/19

6) Rwsecy

[illegible]

4475/1-2-19.

7) Dewan)

hm 10.2.19

MM

NOTE—Contn. sheet.

WD A 1789—GPB—60,000—20-3-18—S.

A B S T R A C T.

Items of work.	Per.	Rate.	Quantity.	Cost.	Total.
BRIDGE OF 5 ARCHES 30' SPAN.					
1. Earth work clearing & excavating foundation.	Cyd.	- 3 -	2689	504	
2. Surki Concrete foundation.	Cft.	- 4 -	3722	931	
3. Stone in surki mortar foundation	Cft.	- 5 -	13116	4099	
4. do. superstructure.	Cft.	- 6 -	8958	3359	
5. Burnt stone slabs 6" dressed.	Sft.	- 10 -	2597	1623	
6. Burnt Brick in sarki mortar	Cft.	- 4 6	9518	2677	
7. Special moulded arch brick in surki mortar	Cft.	- 14 -	6326	5535	
8. Surki mortar pointing.	Sft.	2 8 -	315	79	
9. do. plastering.	"	3 8 -	790	277	
10. Centring charges 1/3 the cost of arch.	L.S.	Rs.	..	1850	
11. Cornice 12" deep.	Rft.	1 4 -	396	495	
12. Baling charges.	L.S.	Rs.		500	
13. Base and Register No. stones.	No.	10 - -	2	20	
14. Gaurd stones complete	No.	6 - -	4	24	
15. Rough stone sujicut apron	Cyd.	1 12 -	246	431	
16. Earth and stone filling over bridge.	Cyd.	- 2 6	285	45	
17. Gravel filling in do.	Cyd.	- 6 -	117	44	
				22493	
II. APPROACH ROADS.					
18. Earth work embankment with watering etc.	Cyd	- 3 -	3420	341	
19. Turfing	Sqr	- 8 -	1012	51	
20 Rough stone revetment.	Cyd.	1 12 -	68	119	
21 Collecting, carting and stacking metal.	"	- 14 -	175	154	
22 do. Gravel	"	- 6 -	22	8	
23. Spreading and consolidating metal	"	- 4 -	175	44	
24 do. Gravel.	"	- 4 -	22	6	
25 Collecting and spreading sand.	"	- 6 -	4	2	
26 Diverting road and maintenance	L.S.			250	
27 Acquisition of land.	L.S.			250	
				1525	
		Total. ..		24,018	
		Contingencies.		1,122	
		Grand total.			Rs.25,140

4

Is it not usual to submit the
paper to H. H before sending
orders?

What is the usual practice?

Yours R. & S.

Please refer this
to Mr. R. N. D.

G.R.S. III—3]

ROUTINE NOTES

[To be used only for notes, requisitions, etc., not intended for permanent record.]

Submitted

S/ The estimates has to be sanctioned by H.E. (vide flag A) in pursuance of sanction of the Chief Engr & the amount is required to (estimates).

9/2 S/ As N.W. is not in the Station, this may, if approved, be submitted after the orders is issued

S/ Please put up a draft D.O. N.

MK
7.2.49

S/ Submitted with a draft D.O.

S/
8/2

N.B.—*Should routine notes be written on small slips, the notes must be copied or slips pasted on this form.*

5

S. N.

Subject.

Construction of a bridge across the Vadli stream on the Hassan - Periapatna Kannanore Road.

The Engr. Supdt has submitted an estimate amounting to Rs 25,140. ~~of the Executive Engineer of the Road Division, Mysore~~ for constructing a bridge across the Vadli stream near Periapatna. The Dt Board, Mysore, have agreed to allot a sum of Rs 5000/- for work in the current year. The necessity for the bridge is detailed in the report of the Ex Engr. himself and was accompanies the Chief Engr's letter under reference.

The Temporary member is for sanctioning the estimate and ~~the~~

The Estimate contained in this file amounting to Rs 25140 relating to the construction of a bridge across the Vadli stream in the Mysore District, which the District Board of Mysore have agreed to construct out of their own funds, a sum of Rs 5000/- for which has been provided in the current year's budget of the Dt. Board submitted for the gracious approval of H. H. The Estimate has been sanctioned by the Chief Engr and agreed to by the Temp. member in Council

MK

L

Sir,

I am directed to forward herewith a draft Sanction for the same is also put up in the file. The papers are submitted for orders regarding sanction being accorded to the construction of the bridge.

S/12

7

Submitted to His Highness.

12 The Estimate contained in this file amounting to Rs.25,140 relating to the construction of a bridge across the Vadli Stream in the Mysore District, which the District Board of Mysore have agreed to construct out of their own funds and for which a sum of Rs.5,000 has been provided in the current year's budget of the District Board, is submitted for the gracious approval of His Highness.

2. 13 The Estimate has been scrutinised by the Chief Engineer and agreed to by the Temporary Member of Council.

Page 2 of the Notes

17.2.19

8

Record of Cases submitted for the Orders of His Highness the Maharaja.

Subject.

14) Estimate amounting to Rs.25,140/- for constructing a bridge across the - Vadli stream in the Mysore District.

Order.

15) Issue
19. 2. 19.

16) Revised
20.2

17) Issue orders accdg
20.2.19

18) Issue sanction
1/2

G. R. S. III-2]

General and Revenue Secretariat. | L. B File No. 76 of 1918.

Serial No.

To the Chief Engineer & Mysore
" Comptroller to Govt.
" President, Dt Bd. Mysore
Rio. & 11065 → Dt 21/2/19

Sanctions the estimate amounting to Rs. 25-140/- the charge being met from the funds of the Mysore Dist. Board.

NOTE—Contn. sheet.

M. D. & I. 1765—G.P.B.—60,000—20-8-18—S.

10

33360

Mysore Public Works Department.

Central Office,

Dated Bangalore, 16th January 1919.

No. B. 522.

Enc: 6 { 1 Estimate, 1 Report, 1 Proceedings, 3 Plans

From

The Chief Engineer of Mysore,

Bangalore

To

B.Ramaswamaiya, Esq., B.A., B.L.,

Secretary to Government,

Revenue Department,

Bangalore.

Sir,

I have the honour to forward herewith for favour of sanction the accompanying estimate amounting to Rs 25,140 for constructing a bridge across the Vadli stream on the Hassan-Periapatna-Cannanore road. The estimate is countersigned by the President in token of his approval thereto.

2. The District Board have resolved to allot a sum of Rs 5,000 for the work in the current year.

I have the honour to be,

Sir,

your most obedient servant,

R V Sundaramma

Deputy Chief Engineer of Mysore.

W.W.S.